



County of Greenville

"... At Your Service"

**ADDENDUM #1
Neighborhood Drainage Improvement
Program: Northeast of Downtown Greenville
IFB# 13-08/27/10**

ISSUED: August 20, 2010

NOTICE TO VENDORS:

The following revisions, additions, and clarifications are hereby made part of the Contract Documents for the above-referenced project and shall be taken into account in the preparation of all Responders and executioners of all Work. Responders shall acknowledge receipt of the Addendum in their response.

1. For evaluation purposes, the County will allow the following product(s) to be used on the Woodview Drive Drainage Improvement project:
 - a. N-12 HP Storm Pipe as manufactured by ADS, Inc.
 - b. N-12 HP Pipe shall have a smooth interior and annular exterior corrugations. N-12 HP Pipe shall have a minimum pipe stiffness of 46 pii when testing in accordance with ASTM D2412. Pipe shall be joined with N-12 HP gasketed integral bell & spigot joint. Virgin material for pipe production shall be impact modified copolymer polypropylene conforming with the requirements of ASTM D4101.
 - c. N-12 HP Pipe will be considered a rigid pipe and shall be installed in the same manner as concrete pipe.
2. The Bid Proposal Form for Woodview Drive (page 3) was revised as follows. A revised Bid Proposal Form is attached to this addendum
 - Revised line item 7141114 to read: 24" RCP, Class III *or* 24" HP, N-12 by ADS

END OF ADDENDUM

BID PROPOSAL FORM

Proposal of _____ (hereinafter called "BIDDER"), organized and existing under laws of the State of South Carolina.

To: County of Greenville (hereinafter called "OWNER"). In compliance with your invitation for Bids, BIDDER hereby proposes to perform all WORK for the construction of NDIP 2010 - July Projects in strict accordance with the CONTRACT DOCUMENTS within the time set forth therein, and at the prices stated below.

By submission of the BID, each BIDDER certifies, and in the case of a joint BID each party thereto certifies as to his own organization, that this BID has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this BID with any other BIDDER or with any competitor.

BIDDER hereby agrees to commence WORK under this contract on or before a date to be specified in the NOTICE TO PROCEED and to substantially complete ALL PROJECTS within Ninety (90) consecutive calendar days thereafter. BIDDER further agrees to pay as liquidated damages, the sum of One Hundred (\$100.00) Dollars for each consecutive calendar day thereafter as provided in the General Conditions.

BIDDER acknowledges receipt of the following ADDENDA:

BID SCHEDULE

All work performed as essential to the completion of the intent of the Contract Documents shall be paid for in accordance with the Bid Schedule. No direct payment will be made for work performed which is not shown as a separate Bid Item. All costs shall be included in the various pay items in the Bid Schedule.

Sedgefield Drive

Section	Item	QTY	Unit	Unit Price	Total Price
	Mob, Staking, Clear/Grub/Demo, Excavation				
1031000	Mobilization	1	LS		
1050800	Construction Stakes, Lines & Grades	1	LS		
2012000	*Clear, Grub & Demo within Construction Limits	1	LS		
2023000	Sawcut, Removal & Disposal of Exist. Driveway	40	SY		
2031000	Unclassified Excavation	150	CY		
<i>subtotal</i>	-----	-----	-----	-----	-----
	Base Materials				
3065135	#5 Washed Stone	50	Ton		
3065150	Surge Stone	50	Ton		
3069900	Maintenance Stone	50	Ton		
<i>subtotal</i>	-----	-----	-----	-----	-----
	Drainage & Conc. Work				
7011400	Class 4000 Concrete (pipe collars)	10	CY		
7141113	18" RCP, Class III	30	LF		
7141116	36" RCP, Class III	8	LF		
7191250	4x4 CB, Type 9 w/ manhole*	1	EA		
7204100	Concrete Sidewalk (4" uniform)	5	SY		
7205000	Concrete Driveway (6" uniform)	40	SY		
<i>subtotal</i>	-----	-----	-----	-----	-----
	Erosion Control				
8041100	Hand Placed Rip Rap	150	Ton		
8048210	Geotextile under Rip Rap (Class 2), Type C	150	SY		
8101000	Perm. Seeding (mulched)**	2	MSY		
8151112	Erosion Control Blanket, Class B (channels)	0.5	MSY		
<i>subtotal</i>	-----	-----	-----	-----	-----
	Miscellaneous				
<i>n.a.</i>	Timber Pedestrian Bridge incl. Supports	1	LS		
<i>subtotal</i>					
Total	-----	-----	-----	-----	-----

* includes removal/disposal of existing stone bridge, walls, pipe, catch basin, etc.

Lake Fairfield Drive

Section	Item	QTY	Unit	Unit Price	Total Price
	Mob, Staking, Clear/Grub/Demo				
1031000	Mobilization	1.0	LS		
1050800	Construction Stakes, Lines & Grades	1.0	LS		
2012000	Clearing & Grubbing within Construction Limits	1.0	LS		
2023000	Sawcut, Removal & Disposal of Exist. Pavement	85.0	SY		
<i>subtotal</i>	-----	-----	-----	-----	-----
	Pavement Patching				
3050106	Graded ABC, 6" uniform	120.0	SY		
4011004	Liquid Asphalt Binder PG64-22	1.0	Ton		

4020330	Hot Mix Asphalt Intermediate Course, Type C	16.0	Ton				
<i>subtotal</i>	-----	-----	-----	-----	----		
	Drainage, Sewer & Conc. Work						
7141794	18" HDPE, Type S	136	LF				
7191250	4x4 CB, Type 9 w/ manhole	1	EA				
7192260	4x4 JB w/ manhole	1	EA				
n.a.	6" PVC (SDR35)	115	LF				
n.a.	12" Square Modular CB w/ grate	2	EA				
7205000	Concrete Driveway (6" uniform)	310	SY				
<i>subtotal</i>	-----	-----	-----	-----	----		
	Erosion Control						
8041100	Hand Placed Rip Rap	50	Ton				
8048210	Geotextile under Rip Rap (Class 2), Type C	30	SY				
8101000	Perm. Seeding (mulched)**	1	MSY				
8153000	Silt Fence	100	LF				
<i>subtotal</i>	-----	-----	-----	-----	----		
	Miscellaneous						
8071000	Reset Wood Fence (6'H)	25	LF				
8072000	Reset Chain Link Fence (4'H)	150	LF				
Total	-----	-----	-----	-----	----		

Woodview Drive

Section	Item	QTY	Unit	Unit Price	Total Price
	Mob, Staking, TC, Clear/Grub/Demo				
1031000	Mobilization	1	LS		
1050800	Construction Stakes, Lines & Grades	1	LS		
1071000	Traffic Control	1	LS		
2023000	Sawcut, Removal & Disposal of Exist. Pavement	300	SY		
2024100	Remove & Dispose of Exist. Curb	50	LF		
<i>subtotal</i>	-----	-----	-----	-----	----
	Pavement Patching				
3050104	Graded ABC, 4" uniform	60	SY		
3050106	Graded ABC, 6" uniform	240	SY		
4011004	Liquid Asphalt Binder PG64-22	3.0	Ton		
4020330	Hot Mix Asphalt Intermediate Course, Type C	35.0	Ton		
4030340	Hot Mix Asphalt Surface Course, Type C	10.0	Ton		
<i>subtotal</i>	-----	-----	-----	-----	----
	Drainage & Conc. Work				
7141114	24" RCP, Class III (or 24" HP, N-12 by ADS)	370	LF		
7165300	Replace Exist. SS w/ 6" DIP*	10	LF		
7191250	4x4 CB, Type 9 w/ manhole*	2	EA		
7191605	Type 16 CB*	1	EA		
7192021	2x3 DI w/ 4x4 box	2	EA		
7203110	Concrete Curb	50	LF		
n.a.	Drainage Bump at Driveway	40	LF		
<i>subtotal</i>	-----	-----	-----	-----	----
	Erosion Control & Misc.				
8041100	Hand Placed Rip Rap	30	Ton		
8048210	Geotextile under Rip Rap (Class 2), Type C	35	SY		
8072000	Reset Chain Link Fence (5' H)	20	LF		
8101000	Perm. Seeding (mulched)**	1	MSY		

8151112	Erosion Control Blanket, Class B (channels)	0.1	MSY				
8152004	Inlet Structure Type F, Weighted	50	LF				
8153000	Silt Fence	50	LF				
<i>subtotal</i>							
Total	-----	-----	-----	-----	-----		

Notes:

- 1.) **Item 1031000, Mobilization, to include any unspecified moving items including but not limited to: moving/resetting temporary obstructions such as mailboxes, road signs, landscape timbers, etc. Also, this line item to include testing (subgrade compaction, concrete, asphalt, etc.) which is to be the responsibility of the Contractor as set forth in Division I, Section 4C, Special Conditions of the bid documents.**
- 2.) **Item 1071000, Traffic Control, to include all construction signs, cones, barrels, barricades, flagmen, etc. as necessary to accomplish the work in a safe manner according to SCDOT and MUTCD guidelines.**
- 3.) **Item 7165300, Replace Exist. SS Main with 6" DIP, to include all materials, equipment, labor, and incidental costs including bedding new DIP with washed stone (24" thick X 36" wide per LF) and neoprene couplings with stainless steel bands. This item consists of 10' replacement at 1 location for a total of 20 LF.**
- 4.) **Item 8101000, Permanent Seeding (mulched), to include fertilizer, lime and straw mulch as set forth in the grassing specifications.**

Project Total

Sedgefield Drive	\$.	
Lake Fairfield Drive	\$.	
Woodview Drive	\$.	
Total	\$.	

BIDDER ACKNOWLEDGES READING THE “INSTRUCTIONS TO BIDDERS”, “BID SCHEDULE”, AND “AGREEMENT”, AND IS IN AGREEMENT WITH THE CONDITIONS OF EACH.

Failure to complete, sign and return this page will cause the bid to be non-responsive and ineligible for award consideration.

PROPOSAL SIGNATURE (All persons submitting proposals for this project shall sign below)

Legal Entity

Signature

Printed Name

SEAL - If Corporation

P.O. Box

Street Address

City, State, Zip Code

Telephone #

Fax #

S.C. Contractors License #

Federal ID#

S.C. Sales Tax #

**FAILURE TO COMPLETE AND RETURN THIS PAGE WILL RESULT IN
YOUR BID NOT BEING CONSIDERED FOR AWARD.**