



County of Greenville

"... At Your Service"

**ADDENDUM #1
Kelsey Glen Subdivision
Phase I & II Project
IFB #26-03/04/10**

ISSUED: February 17, 2010

NOTICE TO VENDORS:

The following revisions, additions, and clarifications are hereby made part of the Contract Documents for the above-referenced project and shall be taken into account in the preparation of all Responders and executioners of all Work. Responders shall acknowledge receipt of the Addendum in their response.

- 1. A new line item has been added to the Scope of Work.**

II. Scope of work:

- A. 12. Removal of existing storm drainage pipes and replacement with new storm drainage pipe.**

The contractor shall be responsible for the removal and the replacement of existing storm drainage pipes and cross lines to ensure proper elevations and to eliminate sag in the lines. The Contractor will be responsible for any asphalt removal and patching associated with the work herein.

- 2. The following items have been added to the Bid Sheet. The quantities listed are estimated. A new Bid sheet is attached.**

Remove and replace existing 18" pipe CB 1 to CB 2	35 LF
Remove and replace existing 18" pipe CB 89 to CB 91	107 LF
Remove and replace existing 18" pipe CB 94 to CB 95	31 LF
Remove and replace existing 18" pipe CB 105 to CB 106	90 LF

END OF ADDENDUM



KELSEY GLEN SUBDIVISION PHASE I & II PROJECT
IFB# 26-03/04/10
Bid Sheet

Line	Item	Quantity	Unit	Unit Price	Total Price
	Kelsey Glen Subdivision Phase - I				
	Mobilization and Traffic Control	1	LS		
	General Site Clearing and Cleaning	1	LS		
	Repair Catch Basin Throat	1	Ea		
	Remove Silt and Repair Slopes within the R/W	1	LS		
	Remove and Install new Silt Fence	280	LF		
	Clean & Stabilize slopes Detention Pond #1	1	LS		
	Grout Cracked Rolled Curb	18	Ea		
	Remove & Replace damaged 18" Rolled Curb	163	LF		
	Remove & Replace damaged Sidewalk	10	LF		
	Install Temporary Cul-de-sac	1	Ea		
	Install New Sidewalk	3180	LF		
	4' Vinyl Coated Chain Link Fence With Gates	404	LF		
	3" Asphalt Binder FDR	15	SY		
	200 lb Asphalt Surface	1040	Tons		
	Stop Sign	2	Ea		
	Street Name Sign	2	Ea		
	Hydro Seed Lots	46	Ea		
	Mow within R/W	2	AC		
	Engineering certifications and as built	1	LS		
	TOTAL				
	Kelsey Glen Subdivision Phase - II				
	Mobilization and Traffic Control	1	LS		
	General Site Clearing and Cleaning	1	LS		
	Remove Silt and Repair Slopes within the R/W	1	LS		
	Remove and Install new Silt Fence	310	LF		
	Grout Cracked Rolled Curb	10	Ea		
	Remove & Replace damaged 18" Rolled Curb	60	LF		
	Install Temporary Cul-de-sac	1	Ea		
	Install New Sidewalk	1350	LF		
	200 lb Asphalt Surface	450	Tons		
	Hydro Seed Lots	42	Ea		
	Mow within R/W	1	AC		
	Engineering certifications and as built	1	LS		
	Remove and Replace 18" RCP at CB-1 to CB-2	35	LF		
	Remove and Replace 18" RCP at CB-89 to CB-91	107	LF		
	Remove and Replace 18" RCP at CB-94 to CB-95	31	LF		
	Remove and Replace 18" RCP at CB-105 to CB-106	90	LF		
	TOTAL				
	TOTAL Phase I & II				
	Option (A)				
	Repair & Stabilize Slopes Basin #2 & #3	2	Ea		
	TOTAL				