Exhibit "A"
To Subdivision
Agreement
To 1226 PAGE 756

PLANTATION PIPE LINE COMPANY

Division Office P. O. Box 130 Castonia, NC 28053

SPECIFICATIONS AND CONDITIONS FOR PIPE LINE CROSSINGS

- 1. It is understood and agreed that this permit is granted only to the extent of Plantation's rights or interest and without warranty.
- 2. The line crossing Plantation's line(s) will be laid under Plantation's line(s) with a minimum clearance of twenty-four (24) inches between the bottom of Plantation's pipe(s) and the top of the line(s) crossing under Plantation. The top of Plantation's line(s) is located approximately two (2) feet below the surface of the ground. This depth, of course, will vary at different points along Plantation's system; however, and regardless of the depth of said line(s), the line(s) crossing under Plantation must be installed at least two (2) feet below and as nearly as possible (but in no event varying more than ten (10) degrees) at right angles to Plantation's line(s). This depth below Plantation's line(s) is to be maintained for the full distance across the pipeline confinement strip, in this instance 50 feet.
- 3. Agreement and acceptance of the above condition must be acknowledged prior to the beginning of any work within the confines of Plantation's pipeline confinement strip, and the crossing company will not operate nor allow to be operated any excavating machinery upon, or within five (5) feet of Plantation's pipeline on either side thereof. The use of explosives will not be permitted within the pipeline confinement strip, and any use of explosives in the general area of the pipeline will be conducted in a manner so as to avoid any damage to Plantation pipeline facilities. Further, the crossing company will mark the location of the underground crossing on each side of Plantation's right of way at the crossing.
- 4. It is understood that Plantation does not, by consenting to the proposed installation of this underground facility across its pipeline confinement strip and underneath its facilities, assume any responsibility for the protection of its pipeline. Furthermore, all work performed in connection with this installation will be without expense, risk, or liability to Plantation or any of its directors, officers, agents, representatives, or employees.
- 5. The crossing company, or its agent, will give a representative of Plantation's Division Office, at the above address, telephone number 704/864-2603, reasonable notice of the day on which the crossing(s) will be made, in order that arrangements can be made of necessary representative of Plantation to be present.
- 6. As soon as practicable after the crossing installation is completed, the crossing company will furnish Plantation with a plat showing the "as-in" location of its line(s) at each crossing in respect to Plantation's pipeline(s) as to angle, depth, station number, etc. Plantation's pipeline station number may be obtained from its representative present at the time the crossing is made.

NOTE: Plantations' system at this point consists of three(3) line(s).

OFFICIAL SIGNING AGREEMENT ON BEHALF OF CROSSING COMPANY MUST INITIAL AND DATE THESE SPECIFICATIONS.

the state	Date	. 1'
		o en भट्टत स्टब्स

W

~(