

ARDWARE

7	ea.	4" iron coll's 8"
1	ea.	3/8x9 1/2-19' filter plate
1	roll	Kenil wire
1	box	wall ties
114	lft.	5" G.I. gutter
106	lft.	downspout
7	ea.	splash block

Specs. attached to plans

CE

BOOK 20 PAGE 1025

3	ea.	L36A majestic
128	bft.	1x6- vertical redwood

180	lft.	2x12-	
1090	lft.	2x10-	sills, sinder & heat plates, etc.
3000	lft.	2x4-	structural beam
1	ea.	6x12-20'	
50	lft.	2x8-	ridge
57	lft.	2x10-	ridge
150	lft.	2x4-	ceclure
66	pc.	2x10-12'	
62	pc.	2x10-14'	
2091	sqft.	1/2x4x8 CD sheathing plywood	
62	pc.	5/8x4x8 underlayment plywood	
850	pc.	2x4- p.o. studs	
80	pc.	3/4"x4x8 styrofoam sheathing	
2	pc.	4x4-8" post	
27	pc.	2x8-22' garage ceiling	
18	pc.	2x8-32' rafters	
16	pc.	2x8-28' "	
26	pc.	2x8-20' "	
23	pc.	2x8-18' "	
36	pc.	2x8-16' "	
23	pc.	2x8-8' "	
8	pc.	2x8-6' "	
2766	sqft.	1/2x4x8 CD sheathing plywood	
8	rolls	15# felt	
30	sq.	roofing	
3125	bft.	1x6- siding	50

E, SHEETROCK & INSULATION

410	lft.	1x10- C&B
170	lft.	1x4- C&B
8	pc.	3/8x4x8 AC exterior plywood
21	pc.	continued eve vent 80
5	pc.	continued ridge vent 100
2	ea.	connectors
6	ea.	end plugs
9707	sqft.	1/2" sheetrock
11	ea.	5 gal. joint cement
14	rolls	sheetrock tape
4	ea.	sheetrock corner beads
3216	sqft.	3 1/2" insulation
1495	sqft.	6" insulation
2	pc.	2x12-12' #1KD
2	pc.	2x12-6' #1KD
3	pc.	1x10-12' C&B
12	pc.	42" oak step tread RT/1 end