



MORRIS CONSTRUCTION COMPANY
219 NORTH PLEASANTBURG DRIVE
GREENVILLE, SOUTH CAROLINA 29606

BOOK

20 PAGES 1222

November 25, 1985

P.O. BOX 5297
862 232 7411

Proposal

Dalton, Morgan, Shook and Partners
114-1/2 West Fifth Street
Charlotte, N.C. 28202

Attn: Mr. Greg Long

Re: Parking Lot
Your Project No. 8015
Our Job No. 2961

Dear Greg,

We propose to furnish all labor, materials, taxes, insurance, tools, equipment, services and supervision in accordance with your Drawing SP-1, SP-2, SP-3, and SP-4 for the following prices indicated.

- ✓A. Parking Lot. Amount \$14,210.00
1. Grade site to proper elevation.
 2. Install approximately 345 L.F. of curb and gutter.
 3. Install approximately 1,045 S.Y. of asphalt with 4" base.
 4. Install concrete gutter at alley.
 5. Patch asphalt at drive entrances and alley as gutter.
 6. Paint approximately 520 L.F. of parking lines.

Note: We have not included paving alley.

- ✓B. Sidewalk at Parking Lot on East North Street side. Amount \$ 3,202.00
1. Remove existing concrete sidewalk.
 2. Install approximately 780 S.F. of sidewalk (104' x 7.5').
 3. Score sidewalk as shown and install expansion joint as called for.
 4. Remove and reset 12 L.F. of granite curb.

- ✓C. Sidewalk at Parking Lot on Brown Street Side. Amount \$ 3,000.00
1. Remove approximately 96 L.F. of granite curb.
 2. Clean and reset approximately 47 L.F. of granite curb.
 3. Install approximately 440 S.F. of 4" thick sidewalk.
 4. Score sidewalk as shown and install expansion joint as shown.
 5. Patch asphalt as necessary.

Since 1899

DMH