

The Subcontractor's Work on this Project shall consist of the following portions of the Project:

**Scope of Work:**

Provide all labor, material, equipment, adequate supervision, and all incidentals necessary to install a 3/4" concrete topping over the existing concrete floor slab. This work includes, but is not specifically limited to the following:

- Scarify the existing floor slab approximately 1/8" to 1/4" in depth.
- Provide and install epoxy bonding agent.
- Place, finish and cure topping approximately 3/4" thick. Tolerance of topping slab to be 3/16" depression maximum under a ten foot straight edge. Concrete topping shall have trap rock aggregate.
- Saw cut floor topping to match exist construction and control joints.
- Special care shall be taken to assure that the concrete topping elevation matches the top of existing concrete elevation at the four door locations.
- It is understood that the racks in the freezer will remain in place during the placement of the concrete topping.

All work shall be done in accordance with the Baker Specifications attached as Exhibit C as required for a complete project.

Baker Concrete will warrant floors against defects of material or workmanship for a period of two years.

Sales tax included.