

9. PARTITION FRAMING:  
 Studs: wood, grade, and species #2 SYP-Dry size and spacing 2"x4"-16"O/C VOL 21 PAGE 693  
 Additional information:

10. CEILING FRAMING:  
 Joists: wood, grade, and species 2"x6" Spruce Other \_\_\_\_\_ Bridging \_\_\_\_\_  
 Additional information:

11. ROOF FRAMING:  
 Rafters: wood, grade, and species 2"x6" Spruce Roof trusses (see detail): grade and species \_\_\_\_\_  
 Additional information:

12. ROOFING:  
 Sheathing: wood, grade, and species 1/2" OSB - Sheathing ;  solid;  spaced \_\_\_\_\_" oc.  
 Roofing Fiberglass ; grade CLASS "A" ; size 12x36 ; type Self-seal  
 Underlay Felt ; weight or thickness 15 ; size \_\_\_\_\_ ; fastening Galv.  
 Built-up roofing \_\_\_\_\_ ; number of plies \_\_\_\_\_ ; surfacing material \_\_\_\_\_  
 Flashing: material Aluminum ; gage or weight .0013 ;  gravel stops;  snow guards  
 Additional information:

13. GUTTERS AND DOWNSPOUTS:  
 Gutters: material Aluminum ; gage or weight .026 ; size 3"x5" ; shape Rectangular  
 Downspouts: material Aluminum ; gage or weight .026 ; size 3"x5" ; shape Rectangular ; number As Req.  
 Downspouts connected to:  Storm sewer;  sanitary sewer;  dry-well.  Splash blocks: material and size 12"x24" Concrete  
 Additional information:

14. LATH AND PLASTER  
 Lath  walls,  ceilings: material \_\_\_\_\_ ; weight or thickness \_\_\_\_\_ Plaster: coats \_\_\_\_\_ ; finish \_\_\_\_\_  
 Dry-wall  walls,  ceilings: material Gypsum ; thickness 1/2" ; finish Smooth/Taped/Painted ;  
 Joint treatment \_\_\_\_\_

15. DECORATING: (Paint, wallpaper, etc.)

ROOMS	WALL FINISH MATERIAL AND APPLICATION	CEILING FINISH MATERIAL AND APPLICATION
Kitchen	<u>1/2" Sheet Rock-Taped/Sealed/Painted-</u>	<u>1/2" Sheet Rock-Textured Ceiling Finish</u>
Bath	<u>1/2" Sheet Rock-Taped/Sealed/Painted-</u>	<u>1/2" Sheet Rock-Textured Ceiling Finish</u>
Other <u>ALL</u>	<u>1/2" Sheet Rock-Taped/Sealed/Painted-</u>	<u>1/2" Sheet Rock-Textured Ceiling Finish</u>
<u>GARAGE</u>	<u>1/2" Sheet Rock-Taped/Sealed/Painted-</u>	<u>1/2" Sheet Rock-Textured Ceiling Finish</u>

Additional information: Stain All Cabinets - Paint All Woodwork - 2 Coats

16. INTERIOR DOORS AND TRIM:  
 Doors: type 6 Panel-Moulded ; material Hardboard-Elite ; thickness 1 3/8"  
 Door trim: type Moulded ; material WP Base: type Moulded ; material WP ; size 3 1/2"  
 Finish: doors Painted ; trim Painted  
 Other trim (item, type and location) \_\_\_\_\_  
 Additional information: (1) Interior Glass Pocketdoor (1) Interior 4'0" Glass Door Unit

17. WINDOWS:  
 Windows: type Insulated ; make Victor-Double Hung material White Pine(WP) ; sash thickness (2) 1/8"  
 Glass: grade "A" ;  sash weights;  balancers, type Integral ; head flashing .0013 Alum.  
 Trim: type Moulded ; material WP Paint Glidden ; number coats 2  
 Weatherstripping: type Alum./Neoprene ; material Solid Storm sash, number \_\_\_\_\_  
 Screens:  full;  half; type Alum./Mobile ; number EA. Hd. ; screen cloth material Aluminum  
 Basement windows: type \_\_\_\_\_ ; material \_\_\_\_\_ ; screens, number \_\_\_\_\_ ; Storm sash, number \_\_\_\_\_  
 Special windows \_\_\_\_\_  
 Additional information:

18. ENTRANCES AND EXTERIOR DETAIL:  
 Main entrance door: material WP (Custom) ; width 3'0" ; thickness 1 3/4" Frame: material WP ; thickness 5/4"  
 Other entrance doors: material WP ; width 3'0" ; thickness 1 3/4" Frame: material WP ; thickness 5/4"  
 Head flashing .0013 Aluminum Weatherstripping: type Neoprene/Alum. ; saddles Bronze  
 Screen doors: thickness 1 1/4" ; number 1 ; screen cloth material FG Storm doors: thickness \_\_\_\_\_ ; number \_\_\_\_\_  
 Combination storm and screen doors: thickness \_\_\_\_\_ ; number \_\_\_\_\_ ; screen cloth material \_\_\_\_\_  
 Shutters:  hinged;  fixed. Railings Oak (Interior) ; Attic louvers \_\_\_\_\_  
 Exterior millwork: grade and species Spruce/Clear Paint Glidden ; number coats 2  
 Additional information: (1) 12'0" Special Glass Door Unit - (FR)

19. CABINETS AND INTERIOR DETAIL:  
 Kitchen cabinets, wall units: material Oak ; lineal feet of shelves Per Plan shelf width 12"  
 Base units: material Oak ; counter top Ceramic ; edging Oak  
 Back and end splash Oak Finish of cabinets Stain/Sealed ; number coats 3  
 Medicine cabinets: make \_\_\_\_\_ ; model \_\_\_\_\_  
 Other cabinets and built-in furniture Vanity Each Bath, Desk, Bookshelves (Family Room)  
 Additional information: Bath Tops - Marble

20. STAIRS:

STAIR	TREADS		RISERS		STRING		HANDRAIL		BALUSTERS	
	Material	Thickness	Material	Thickness	Material	Size	Material	Size	Material	Size
Basement	YP	1"	WP	3/4"	YP	2x10	Oak	3"x3"	Oak	1"
Main										
Attic										

Disappearing: make and model number A-100 Atlas  
 Additional information: Stair Skirts - Oak

SPECIFICATIONS

APPROVED AND ACCEPTED

*S. Brennan*  
*Mari L. Brennan*

