

16. INSULATION:

LOCATION	THICKNESS	MATERIAL TYPE, AND METHOD OF INSTALLATION	VAPOR BARRIER
Roof			
Ceiling		R-30 Fiberglass	Kraft
Wall		R-13 Fiberglass	Poly
Floor		R-19 Fiberglass	Kraft

27. MISCELLANEOUS: (Describe any main dwelling materials, equipment, or construction items not shown elsewhere, or use to provide additional information where the space provided was inadequate. Always reference by item number to correspond to numbering used on this form.)

All Faucets - Delta Single Lever - Chrome Prewire Phone
 Wallpaper Allowance: \$1600.00 Installed Prewire TV - Wire Only
 Dead Bolt Locks - All Exterior Doors 9' Ceilings 1st Floor-8' Ceilings 2nd Flr.
 (1) Pair Shutters (Front) Bull Nose Brick: Front-Window Sills
 Custom Front Door - \$600.00 Allowance
 Crown Mould: Dr, LR, Foyer: 3 PC Crown - All Other Rooms-1st Floor-(2) PC Crown Mould
 Chair Rails: Foyer, Dr, HBR, Hall 2nd Floor Crown Mould 5" - (2) PC
 (5) 2040 Skylights Mirror over each laboratory
 Bath Tops: Marble Mirror over wet bar
 HARDWARE: (make, material, and finish.) Schlage and Weiser - Polished Brass - Brass Kick Plate, Front Door

SPECIAL EQUIPMENT: (State material or make, model and quantity. Include only equipment and appliances which are acceptable by local law, custom and applicable FHA standards. Do not include items which, by established custom, are supplied by occupant and removed when he vacates premises or chattles prohibited by law from becoming realty.)

Appliances: \$2400.00 Allowance-Builder Cost - Custom Light Boxes, Kitchen, Bref. Area
 Brick Quoins: Front house corners - Intercom System-\$2000.00-Installed Allowance
 Built-in Ironing Board
 Steps: Carpet Runners - Oak Trim
 Ice Maker Connection - Kitchen and Wet Bar
 Fiberglass Screen - Rear Porch
 Exterior Floodlights - Main House Corners

SPECIFICATIONS
APPROVED AND ACCEPTED
RBB

PORCHES:

Per Plan - Brick Pavers, Front Porch, Screen Porch, Installed Allowance: \$6.50 sq. ft.

TERRACES:

GARAGES:

Per Plan: Concrete Floor, Sheet Rock Walls and Ceiling (3) 9'0" Doors, Electric Door Openers - Each Door

WALKS AND DRIVEWAYS:

Driveway: width 10'0"; base material Gravel; thickness 2"; surfacing material Asphalt; thickness 2"
 Front walk: width 42"; material Concrete; thickness 4". Service walk: width 36"; material Concrete; thickness 4"
 Steps: material Brick; treads 10"; risers 7". Check walls ---
 Driveway: 10'x90' Asphalt

OTHER ONSITE IMPROVEMENTS:

(Specify all exterior onsite improvements not described elsewhere, including items such as unusual grading, drainage structures, retaining walls, fences, railings, and accessory structures.)

Brick Mail Box Post
 Walkway: Screen porch -- garage door-36" wide - Concrete

LANDSCAPING, PLANTING, AND FINISH GRADING:

Topsoil _____" thick: front yard; side yards; rear yard to _____ feet behind main building.
 Lawns (seeded, sodded, or irrigated): front yard; side yards; rear yard
 Planting: as specified and shown on drawings; as follows: Landscape Allowance: \$3000.00
 Shade trees, deciduous, _____" caliper. _____ Evergreen trees. _____' to _____', B & B.
 Low flowering trees, deciduous, _____' to _____'. _____ Evergreen shrubs. _____' to _____', B & B.
 High-growing shrubs, deciduous, _____' to _____'. _____ Vines, 2-year
 Medium-growing shrubs, deciduous, _____' to _____'. Grading Allowance: \$2200.00
 Low-growing shrubs, deciduous, _____' to _____'.

IDENTIFICATION.—This exhibit shall be identified by the signature of the builder, or sponsor, and/or the proposed mortgagor if the latter is known at the time of application.

Date _____

Signature R. Bruce Beerman
R. BRUCE BEERMAN

Signature _____
AUDREY V. BEERMAN

