J.A. Pierce Ent., Inc.
508-A Union Street
Spartanburg, S.C. 29301-4418
(803) 583-4211

BIL CHANGES

VOL 21 PAG 219
Pg. 5

27) Additional 8" CMU walls and related demo, etc. as described. Price includes layout, ordering materials, cost of block, lintels, sand, mortar, durowall, RS-bar floor dowels, pour concrete bond beam, various steel connectors for tie-in's at existing walls. Pour bottom 2 courses of block solid, pour corners solid, and install #4 rebar in corners.

A) Across line 7 · Build around window, pass thru & 1 door $1400.00
B) Additional chase wall in N.E. corner of line 7 · Build around duct. 750.00
C) Continuation of double chase wall dividing 6 & 7. Build around duct & pass thru. Install s/s pipe sleeve. Shed wall tie-in. 1250.00
D) After Daley has saw cut for new openings, we demo & brace new opening in North wall line 6 for 1 - 3'7" door and re-build walls around same. Double lintels, rebar, etc. 1100.00
E) Demo & brace new opening in North wall line 7 for 1 - 6'7" door. A 3'7" door was installed instead & lgr. opening blocked in. 1400.00
F) Demo & brace new opening in North wall line 7 for an additional 3'7" door, rebuild wall, etc. 1100.00

$7000.00

28) Supply and install 1 additional s/s window frame & pass thru box in line 7 to duplicate line 6. (Quoted to WHC 2/9/88) 3,250.00