

B&L CHANGES

J.A. Pierce Ent., Inc.
508 A Union Street
Spartanburg, S.C. 29301-4418
(803) 583-4211

VOL 21 PAGE 20
Pg. 6

- 29) SUPPLY AND INSTALL MRS LEXAN AND #800 COMMUNICATOR IN DOUBLE WINDOW LINE #7. (QUOTED TO WHC 2/9/88) \$ 1652.00
- 30) INSTALL WHC SUPPLIED 4 S/S DOOR FRAMES, DOORS & FINISH HARDWARE AND 1 S/S PASS THRU IN DOUBLE CHASE WALL. (4 @ 325.00 = 1300.00 + 1 @ 100.00) = 1400.00
- 31) CONCRETE SAW CUTTING FOR NEW OPENINGS IN NORTH WALLS. 1230.00
- 32) WET GRIND LINE #7 AND COMPLETE PACKAGING ROOM. 3200 S.F. @ 1.25 4000.00
- 33) CORE DRILL AND EPOXY GROUT FILL SEVERAL EXISTING THUNDERSTUD BOLTS FROM FLOORS IN LINES 6 & 7 AND PKG. ROOM. (E. PRILLIQ) 356.12
- 34) DELETE R-11 INSULATION IN LINE 6 CEILING AND ADD R-19 INSULATION FACED BATTS. 480.00
- 35) EPOXY GROUT TO REPAIR BADLY GOUGED AREAS IN FLOORS LINES 6 & 7 AND PKG. ROOM. BUILD OUT FOR BASE ON OLD EXISTING WALLS. 789.60

JAP

