



HOWE FIRE APPARATUS CO.

Manufacturers of Fire Apparatus Since 1872
ANDERSON, INDIANA, U. S. A.

HOSE BODY

Hose body is made of 12 gauge cold rolled stretcher level body steel. The base supporting the hose body is steel welded channel construction to give exceptional rigidity to the hose body and form a solid base for the booster tank. The entire hose body is covered with a hard wood slatted removable floorboard. The body is fully streamlined at the rear, with the body panels especially formed with a concealed break to give exceptional strength, yet accentuating the overall streamlined effect of the fire truck. The capacity of the hose body is ~~1000~~ ¹⁰⁰⁰ ft. 2 1/2" D. J. and ~~300~~ ³⁰⁰ ft. 1 1/2" D. J. fire hose.

Partition in hose body to separate 2 1/2" and 1 1/2" hose.
1 1/2" preconnected wet line to rear of 1 1/2" compartment.

RAILINGS

1 1/4" polished ~~existing around the full length of the hose body, concealed in the contour of the streamlining at the rear of the body~~ to furnish hand grips for firemen riding on the running board and steps. The hose body posts at the rear are ~~Painted red~~ ^{Painted red}.
One Cross rail at rear to provide hand grab for firemen riding on the rear step.
Grab rails on each side of closed cab.

REAR FENDERS, REAR STEP & RUNNING BOARDS

The rear step and running boards are constructed with a special safety tread which is absolutely non-slip. The steps and running boards, as well as the fenders, are fully enclosed to protect the firemen from flying mud. The rear fenders are of crown type. The entire running board, rear step, and fender assembly is securely bolted to channel and angle iron supports. The series of channel and angle iron supports which support the above assembly are welded in such a manner that in the event of a collision a minimum of disassembly and replacement is required.

EQUIPMENT COMPARTMENTS

One (1) large open compartment back of cab.

Four compartments at front and rear of rear fenders with automatic lights.
One large compartment at rear with two doors and automatic lights.
One door in side of body for easy access to behind cab compartment.

EXTINGUISHERS

F. D. type Fire Extinguishers are mounted in clamp type quick opening holders.
One 15 lb. CO₂, one 20 lb. Ansul dry powder.

(Continued on Next Page)