STATE SOUTH CAROLINA

COUNTY OF GREENVILLE

KNOWN ALL THESE PRESENT:

That the following agreement entered into by and between M. E. Madden mant herein after called and refered to as the Owner, and H. A. Pulliam hereinafter called and refered to as the Centracter.

R. F.O. AGREEMENT OF OWNER AND CONTRACTOR

The centractor hereby agrees to Furnish all Carpenter Labor ENEXAGENCEMENT for the construction of a certain five room house known as the Oxford Plan, on Let Welcome Ave, Greenville County S.C. for the sum of \$1320.00 the contractor agrees to follow and construct according to plans and specifications except where certain miner changes may be deemed wise and necessary provided said Changes shall not lessen the Value of the house and property, however such changes must be agreed upon by owner and Centracter.

Owner agrees to arrange for Purchasing and pay for all materials to be used in the construction of said house, materials are to be placed on lot by owner, so as net te delay centracter, ewner agrees to purchase windewe units complete with screens, centracter dees not agree to build any | base or wall cabinets, centracter agrees to finish with Pearches with concrete, contractor agrees to furnish labor for digging and peuring feeting fer sum of \$35.00 centractor agrees to furnish labor for all Brick work for \$30.00 per Thousand.

Owner agrees to arange for the following at his expense so as not to delay centractor, Plumbing, leating, wireing, Painting, facor finishing tile asbests siding disappearing stairway or any thing else that does not come under carpenter Labor.

Centracter agrees to the following specifications feeting 4" x 12 " centrate foundation Brick floor joint 2 x 8 dressed 16 " O.C. Studs 2 x 4 dressed 16" O.C. Cealing jeint 2 x 6 Dressed 16 " O.C. Tafters 2 x 6 dressed 16 " O.C. sub fleer 1 " Beards dressed, fleer- Oak Fleer L.R.B.D.R. & hall Pine in Kitchen and Bath Exterior walls stemm sheeting Box out side cornice, Interior walls Rock Lath;

The centracter agrees to complete said house by September 1st, 1951 if weather conditions will permit.

Centracter is to be payed within 90 days frm after house is completed .

All Carpenter and masen Laber is to be settled before Contractor is Paid.

In witness Whereof. we hereunte set our hands and seals this 11th day of June 1951.

m & maddin

In the presence of:

State of South Carolina

County of Greenville

Personally comes and made oath that he saw M. H. Madden

and H. A. Pulliam wign the foregoing

uses and purposes therein stated and that he with Witnessed the execution thereof.

SWORN to before me this 23 day

of July, 1951.

CoculeySEAL}

Recorded July 23rd. 1951 at 3:00 P. M.

#17055

I cancelled this Sept. 25, 1957 da P. Mann