



TRUCK ENTRANCE (SHOWN CROSS-HATCHED) TO RECEIVE THE FOLLOWING:
 1" ASPHALT SURFACE
 2" ASPHALT BINDER
 8" STONE BASE

TAP EXISTING 12" WATERLINE. CONTRACTOR SHALL MAKE A 4"x6" CUT IN ROAD SURFACE AND SORE UNDER PAVEMENT AND SIDEWALK TO MAKE 8" WATERLINE CONNECTION

EXISTING ENTRANCE SHALL BE USED AS A CONSTRUCTION ENTRANCE WITH 30"x50"x8" STONE PAD TO BE REPLACED BY SPECIFIED PAVING SECTION

EXHIBIT A

PARKING AREA TO RECEIVE:
 1" ASPHALT SURFACE
 2" ASPHALT BINDER
 4" STONE BASE

NOTE

BOUNDARY AND TOPOGRAPHICAL INFORMATION TAKEN FROM A SURVEY BY PIERMONT SURVEYOR GREENVILLE SC DATED: OCT 7, 1981

0976

1328-17-2