

1. Builder's Risk Insurance (Wickliffe Company)	\$	887.00
2. Multitech Corp. Inc. (Intercom)		2,209.19
3. Insulation of walls and ceiling in garage		251.86
4. Mailbox and post--Material \$36.10, Labor \$35.00		71.10
5. Special cut mould to extend window jambs for interior shutters-- Material \$785.42, Labor \$392.71		1,178.13
6. Cypress raised panel fireplace wall instead of T&G "V" Joint boards		724.50
7. Tuck & Howell Heating & Air Conditioning: Four (4) electronic air cleaners, humidifiers and venting		3,582.85
8. Foister Electrical--Changes and additions (see attached)		2,123.68
9. Architectural Products (Pella)--72 casement crank knobs		529.20
10. Lloyd Hall Plumbing--connecting ice maker, replacing kitchen sink and outside faucet		478.76
11. City of Greenville and Metromont Materials--Piping ditch on East Parkins Mill Road		2,528.94
12. Campbell Tile--Two (2) slate bow front hearths in basement		750.00
13. Total cost of hardware \$6,362.98, less \$4,200.00 allowance		2,162.98
14. Colored concrete in lieu of asphalt--Front drive and garage apron only: 690 sq. yds. asphalt @ \$7.00 -- \$4,830.00 6,200 sq. ft. colored concrete @ \$1.50-- \$9,300.00 -- Difference		4,470.00
15. Back drive and walks--3,272 sq. ft. @ \$1.50		4,908.00
16. Additional retaining walls and columns in rear at Patio: 720 sq. ft. with rowlock top and 8" concrete block backup. All cores poured solid with concrete with #4 rebar @ 16" o.c. Dura-wall 16" o.c. Footings 36"x12".		
5,040 face brick @ \$.35 in wall	\$1,764.00	
840 8" concrete block @ \$1.75 in wall	1,470.00	
Rowlock cap--400 face brick @ \$.40 laid	160.00	
500 lin. ft. #4 rebar @ \$.25	125.00	
1 bundle of 12" dura-wall	96.00	
80 ft. 36"x12" footing--9 yds concrete @ \$48.00=\$432.00 + \$90.00 labor	522.00	
6 yds. chat concrete to pour cores of concrete block-6 yds. @ \$55.00=\$330.00 + \$20.00 yd. labor=\$120.00--total	450.00	
Labor to dig footing and tie steel	160.00	
		4,747.00
		\$31,603.19
1% - Overhead		316.03
10% Contractor's Fee		3,160.32
Total for Extras		\$35,079.54