

## DESCRIPTION OF MATERIALS

## 26. INSULATION:

LOCATION	THICKNESS	MATERIAL, TYPE, AND METHOD OF INSTALLATION	VAPOR BARRIER
Roof	12"	R-30 Fiberglass	Kraft
Ceiling	3 5/8"	R-13 Fiberglass	Poly
Wall	6"	R-19 Fiberglass	Kraft
Floor			

## 27. MISCELLANEOUS: (Describe any main dwelling materials, equipment, or construction items not shown elsewhere, or use to provide additional information where the space provided was inadequate. Always reference by item number to correspond to numbering used on this form.)

All Faucets - Delta Single Lever (Chrome) Cabinet Allowance: \$4,500.00  
 Wallpaper Allowance - \$900.00 Installed  
 Dead Bolt Locks - All Exterior Doors  
 Custom Front Door - \$600.00 Allowance  
 Crown Mould: LR, DR, Foyer, Kit., MBR, FR  
 Chair Rail: Foyer, DR, MBR  
 (2) 2040 Skylights  
 Prewire Phone  
 Prewire TV (7) Stations - Wire Only

HARDWARE: (make, material, and finish.) Schlage and Weiser - Polished Brass - Brass Kick Plate Front Door

## SPECIAL EQUIPMENT: (State material or make, model and quantity. Include only equipment and appliances which are acceptable by local law, custom and applicable FHA standards. Do not include items which, by established custom, are supplied by occupant and removed when he vacates premises or chattels prohibited by law from becoming realty.)

Appliance: Stove, oven, DW, disposer, microwave, compactor, \$2,000.00 Allowance  
 Tray Ceilings: MBR, FR  
 Built-in Ironing Board  
 Wall-to-wall mirror each bath - Lavatory/Vanity Area

## SPECIFICATIONS

APPROVED AND ACCEPTED

J.R. Brennan  
 Marie L. Brennan

## PORCHES:

Per Plan - 6"x6" Ceramic Tile Front Entry Porch

## TERRACES:

Patio: 12'x16' Prox. Treated Lumber with Seat

## GARAGES:

Per Plan: Concrete Floor, sheet rock walls and ceilings (1) 18'0" door, electric opener (2) controls

## WALKS AND DRIVEWAYS:

Driveway: width 16'0"; base material Clay; thickness ---"; surfacing material Concrete; thickness 4"  
 Front walk: width 42"; material Concrete; thickness 4". Service walk: width ---; material ---; thickness ---  
 Steps: material Brick; treads ---"; risers ---". Check walls ---  
 Driveway Length 40'

## OTHER ONSITE IMPROVEMENTS:

(Specify all exterior onsite improvements not described elsewhere, including items such as unusual grading, drainage structures, retaining walls, fence, railings, and accessory structures.)

Brick Mail Box Post

## LANDSCAPING, PLANTING, AND FINISH GRADING:

Topsoil 4" thick:  front yard;  side yards;  rear yard to 35' feet behind main building.  
 Lawns (seeded, sodded, or irrigated):  front yard;  side yards;  rear yard  
 Planting:  as specified and shown on drawings;  as follows: Landscape Allowance: \$1,000.00  
 Shade trees, deciduous, ---" caliper. Evergreen trees, ---' to ---', B & B.  
 Low flowering trees, deciduous, ---' to ---'. Evergreen shrubs, ---' to ---', B & B.  
 High-growing shrubs, deciduous, ---' to ---'. Vines, 2-year  
 Medium-growing shrubs, deciduous, ---' to ---'. Landscape per drawing - plan  
 Low-growing shrubs, deciduous, ---' to ---'. Grading Allowance: \$1,800.00

IDENTIFICATION.—This exhibit shall be identified by the signature of the builder, or sponsor, and/or the proposed mortgagor if the latter is known at the time of application.

Date

4-21-87

Signature

JAMES R. BRENNAN

Signature

MARIE L. BRENNAN