

BIL CHANGES

J.A. Pierce Ent., Inc.  
508 A Union Street  
Spartanburg, S.C. 29301-4418  
(803) 583-4211

VOL 21 PAGE 217

Pg. 3

- 16) DEMO SECTION OF NORTH CMU WALL, REMOVE EXISTING S/S PASS THRU, INSTALL CORE-FILLED 8" CMU'S, REPAINT. (CREDIT ALLOWED FOR COST OF LEXAN IN ORIGINAL QUOTE) ( $\$200.00$  LESS  $\$75.00$ ): \$ 125.00
- 17) Add LIBERTY INDUSTRIES #800 COMMUNICATOR 89.00
- 18) A) Add ONE ADDITIONAL MRS LEXAN WINDOW TO DETAIL  $\frac{B}{1126}$ , S/S STOP AND DESICCANT STRIPS AS NEEDED TO DUPLICATE Lg. WINDOW INSTALLED IN NEW EAST CHASE WALL. THIS NEW WINDOW WILL ONLY BE APPROX. 8 1/4" WIDE IN A SINGLE CMU WALL.
- B) INSTALL COMMUNICATOR IN WINDOW WITH CLEAR LEXAN CYLINDER BETWEEN LEXAN WINDOW PANES TO DUPLICATE OTHER COMPONENTS AS IS EXISTING IN PLANT PACKAGING / FILL ROOMS. 1565.00
- 19) REPAIRS TO BLOUNT SUPPLIED 2 S/S FRAMES 300.00
- 20) INSTALLATION OF BLOUNT SUPPLIED HARDWARE FOR 2 S/S FRAMES AND 4 S/S DOORS, PUSH PLATES, CONCEALED CLOSERS, KICK PLATES AND WEATHERSTRIPPING. 250.00

~~STOP~~

