



USE AGGREGATE NO. 1, 2, 24, OR 3
AS CONSTRUCTION ENTRANCE MATERIAL

UNDERLINING NON-WOVEN GEOTEXTILE FABRIC

TAPER EDGES OUT
TOWARDS ROAD TO PREVENT
TRACKING OF MUD ON THE EDGES

100-FT. MIN.

6-INCH MIN.

24-FT. MIN.

INSTALL A CULVERT PIPE ACROSS
THE ENTRANCE WHEN NEEDED TO
PROVIDE POSITIVE DRAINAGE.

DIVERT ALL SURFACE RUNOFF AND
DRAINAGE FROM THE STONE PAD
TO A SEDIMENT TRAP OR BASIN
OR OTHER SEDIMENT TRAPPING
STRUCTURE.

FOR COUNTY APPROVED ALTERNATIVE
PRE-FABRICATED CONSTRUCTION
ENTRANCES, FOLLOW MANUFACTURER'S
SPECIFICATIONS FOR INSTALLATION
AND MAINTENANCE PRACTICES.



Greenville County
Storm Water Management

CONSTRUCTION ENTRANCE

STANDARD DRAWING NO.

SC-06

APPROVED BY:

GREENVILLE COUNTY STORM WATER MANAGEMENT

January 2018

DATE