

**HOWE FIRE APPARATUS CO.**Manufacturers of Fire Apparatus Since 1872  
ANDERSON, INDIANA, U. S. A.**METAL FINISH, PAINTING AND LETTERING**

All nozzles and similar polished metal parts are chromeplated.

The best grade ~~enamels~~ enamels and finishing materials are used. All metal is thoroughly cleaned and etched before painting with best type of metal treating solution and each coat of paint is thoroughly sanded. All metal is first primed before assembly so that all seams and overlaps are covered by paint before installation, thus preventing rust at the seams. Finish coats are hand sanded and polished to a high gloss. All lettering and decoration is supplied in genuine gold leaf with appropriate shading and is placed on the unit by an artist. The lettering is to order and all lettering and decoration is placed on the truck free-hand. No decals of any type are used. Color: Fire engine red

**LIGHTS, SIGNALING AND ELECTRICAL EQUIPMENT**

2 - Carpenter J-24 lanterns in holders.

Two (2) six inch inside cab controlled swivel electric searchlights mounted on windshield posts.

Two (2) electric swivel hose body lights mounted on rear body posts.

One (1) 21 candle power light over gauges.

One (1) electric siren mounted on top cab with one switches.

Siren Model: Federal Model CLR with front rear red flasher light.

Standard battery supplied with chassis replaced with battery to meet Underwriters specifications.

Turn signals front and rear. 2 tail lights, 2 stop lights.

**MISCELLANEOUS EQUIPMENT**

One (1) set of hose spanner wrenches.

One (1) F.D. axe in holders.

One (1) F.D. crowbar in holders.

One (1) Double Female hydrant connection. 4 x 2 1/2" NST

One (1) highly polished suction strainer.

Two (2) running board flanges for carrying nozzles. 2 1/2" NST

Two (2) running board flanges for carrying suction fittings. 4" NST

Two (2) chrome plated caps for suction of pump.

Two (2) chrome plated caps for discharge of pump.

One set 2 1/2" double male and female adapters

Two (2) 2 1/2" gated suction, one each side with 2 - 2 1/2" soft suction hose mounted in cabinets, one each side.

One (1) 2 1/2" playpipe with ladder holder and Akron PDQ combination nozzle.

One 2 1/2" playpipe equipped with ladder holder and 1-1/8" plain beaded tip.

One 1 1/2" PDQ nozzle

2000' 2 1/2" DJ fire hose with brass rocker lug couplings, NST

400' 1 1/2" DJ fire hose with brass rocker lug couplings, NST

One Federal 2 HP General Alarm Siren 110 volt, 60 cycle

Chrome plated front bumper with tread plate

Custom closed cab with chromeplated front grille

Chromeplated compartment door latches

Electric tank water level gauge

Two underhood lights. One battery recharge plug in.

Form No. 61-4/56 Two all purpose gas mask, smoke cannister, in case.

5M-3/58  
Recorded August 15th, 1958 at 9:00 A.M. # 4401