Exhibit "B"
To Subdivision
Agreement
VOL 1226 PUSE 787

## PLANTATION PIPE LINE COMPANY DIVISION OFFICE P. O. Box 130

GASTONIA NC 28053-0130

## SPECIFICATIONS AND CONDITIONS FOR UNDERGROUND TELEPHONE AND ELECTRICAL POWER CABLE CROSSINGS

1. It is understood and agreed that this permit is granted only to the extent of Plantation's rights or interest and without warranty.

## 2. TELEPHONE CABLE:

- A. The cable crossing Plantation's line(s) will be laid under Plantation's deepest line(s) with a minimum clearance of twenty-four inches (24") between the bottom of Plantation's pipe(s) and the top of the cable installation crossing under Plantation. The crossing shall be as near as possible at right angles to Plantation's line(s) and in no event should vary more than ten (10) degrees.
- B. The telephone cable will be encased for the entire width of Plantation's right of way. EC-PVC duct is preferable; however, other material may be used if approved by Plantation.

## 3. ELECTRICAL POWER CABLE:

- A. The cable crossing Plantation's line(s) will be laid under Plantation's deepest line(s) with a minimum clearance of twenty-four inches (24") between the bottom of Plantation's pipe(s) and the top of the cable installation crossing under Plantation. The crossing shall be as near as possible at right angles to Plantation's line(s) and in no event should vary more than ten (10) degrees.
- B. The cable will be encased for the entire width of Plantation's right of way. EC-PVC duct is preferable; however, other materials may be used if approved by Plantation. Two to four inches of concrete shall be placed around the duct or casing.
- C. Magnesium sacrificial anodes will be installed at each crossing if the cable's concentric neutral is in contact with the soil. Also, a test lead line from the power cable concentric neutral and a test box will be at each crossing. Plantation will furnish and install a test lead line for its pipe(s). If the cable's concentric neutral has an insulating jacket preventing contact with the soil, the anodes, test leads, and test box will not be required.
- 4. Agreement and acceptance of the above conditions must be acknowledged prior to the beginning of any work within the confines of Plantation's right of way, and the crossing company will not operate nor allow to be operated any excavating machinery upon, or within five (5) feet of Plantation's pipeline on either side thereof. Further, the crossing company will mark the location of the underground crossing on each side of Plantation's right of way at the crossing.