
10-22 -34 i

## HORIZONTAL LINE POST INSTALLATION FOR 12.47 KV STRAIGHT LINE AND ANGLES TO 10°

-11,

USE ARMOR RODS ON ANGLES ONLY



This type construction is recommended in specific applications where 24 KV is not anticipated for express feeders where tree conditions are a problem or where appearance is a prime factor. This type construction may utilize the pole top extension.

Bil: Ø to Ø Ø to Ø Ø to grd.

A to C B to A or C B to N A or C to N

Dry-285 KV 305 KV 410 KV 370 KV

Wet-185 KV 198 KV 270 KV . 240 KV

Clamps to be used with horizontal line post for 1/0-336 ACSR are available on Lot #185-306. Clamps for angles  $10^{\circ}-30^{\circ}$  are available on Lot #185-307.

If pole top extension is used with steel plates.

Bil: Ø to grd. Ø to grd.

B to N A or C to N

Dry-250 KV 220 KV

Wet-160 KV 140 KV

Recorded May 2, 1972 At 12:15 P.M. # 29602